

Bid Addenda
Intrusion Alarm System
For
McGuire School
And
Stephen Olney Elementary School

Add door at Kitchen for McGuire School

Door Control key pad can be mounted on the drywall at Stephen Olney School

Work Completed by 7/31/2019 for both schools

Key Pad model number 6160

Building contractor Gilbane will provide that all door contacts will be pre-wired and terminated above drop ceilings at each doors location. Those Gym and Cafeteria doors where there were cement walls will also be pre-wired an those wires will be run and terminated in the common hallway outside those rooms above the drop ceiling.